



NOTES:

1. All drawings are to be read in conjunction with relevant specification and all other drawings.
2. All dimensions and levels to be checked on site and any discrepancies identified prior to the commencement of the works.
3. All dimensions in millimeters unless otherwise noted.
4. All levels in meters unless otherwise noted.
5. Existing footway to be removed to a depth of 80mm and regulated prior to new surface being laid.

LEGEND:

- Footway Resurfacing - 50mm DBM Binder Course (AC Dense Bin 100/150), 30mm HRA Surface Course (HRA 30/14 C Surf)
- Footway Construction - Regulating course to meet levels as per DRG No. RTD/636382/8/020, RTD/636382/8/021, RTD/636382/8/022, 50mm DBM Binder Course (AC Dense Bin 100/150), 30mm HRA Surface Course (HRA 30/14 C Surf)
- New Precast Concrete Road Kerb, 125mm x 255mm HALF BATTER PATTERN - See DWG RTD/636382/1/8/1104 for detail
- Timber edging - 30mm x 75mm to be laid at back of footway

See Drawing No. RTD/636382/1/8/1104 for typical cross sections and details
 See Drawing No. RTD/636382/1/8/020, RTD/636382/1/8/021 and RTD/636382/1/8/022 for cross sections

This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office © Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.
 100023420 (2013)

REVISION	DETAILS	BY	DATE	CHECKED
----------	---------	----	------	---------



SERVICES FOR COMMUNITIES The City of Edinburgh Council City Chambers, High Street Edinburgh EH1 1YJ Tel No 0131 200 2000	TRANSPORT TRAFFIC & ENGINEERING NEW WORKS Roads & Transport Design
--	---

Leith to Portobello Cycleway
Phase 2

Seafield Road - Preliminary Design
Footway Construction and Widening
Drawing 1 of 4

Date: 15 November 2013 Scale: 1:500	Job No.: 636382	Drawn by: D Morton Checked by: D Blair
--	-----------------	---